EXTRA ITEM RATE LIST

ar(: of Work: Drilling of Bore well and Providing Pipeline in Ward No.11 (Kuvempunagara), Vidyaranyapura Sub Division.

ame of Agency: Sri B. Chandrashekar, No. 28, Anjaneyaswamy Layout, 1st Main, Thindlu, Vidyaranyapura (Post), engalruru - 560097.

stimated Cost: 35,00,000.00

ender Amount : Rs. 28,04,266.75 Lakhs

ork Order No. EE/BTP/WO/27/2020-21 Dated: 23-06-2020.

.	Item No.	Description of Work	Unit	Qty	Rate	Amount	Whether the items are alternative to items in tender schedule or whether being an additional item	Wheather the extra items s included in the sanctioned Estimate	How the expenditure due to the extra item is proposed to be met out	Whether the item isincluded in the S.R (Referabce if SR to be given . If not Data Should accompany the EIRL	Remarks
	E1	Earth work Excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work. **(PWD SR 2021-22 Vol -I Pg No 5 item no 1.4.1)**	Cum	7.26	282.75	2052.77	Additional Item	No	By over all savings in the work	PWD SR 2021-22 Volume - II	
	E2	Providing and laying in position Plain Cement Concrete Mix 1:3:6 (M10) for levelling course for all works in foundation. Using 40 mm nominal size graded crushed coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. **(PWD SR 2021-22 Vol -I Pg 15 item no 2.1.3)**	cum	0.73	5560.16	4058.92	Additional Item	No	By over all savings in the work	PWD SR 2021-22 Volume - II	
	E3	Providing Size Stone masonry with hard stone in foundation & plinth with Cement mortar 1:6 (1 cement : 6 coarse sand) **Item No. 5.4, Page No. 9, Vol - II PWD SR 2021-22**	cum	3.06	5428.02	16609.74	Additional Item	No	By over all savings in the work	PWD SR 2021-22 Volume - I	

n NO.	Description of Work	Unit	Qty	Rate	Amount	Whether the items are alternative to items in tender schedule or whether being an additional item	Wheather the extra items s included in the sanctioned Estimate	How the expenditure due to the extra item is proposed to be met out	Whether the item isincluded in the S.R (Referabce if SR to be given . If not Data Should accompany the EIRL	Remarks
E4	Providing ruled pointing to cursed stone masonry with lime mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost all materials, labour, usage charges of machinery, curing complete as pre specification. **Item No. 21.10 Page No. 190, Vol - II PWD SR 2021-22**	sqm	4.80	238.26	1143.65	Additional Item	No	By over all savings in the work	PWD SR 2021-22 Volume - I	
E5	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite / trap / basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately Mix 1:3:6 (M10) Using 20 mm nominal size graded crushed coarse aggregate **(PWD SR 2021-22 Vol - I Pg 15 item no 2.1.4))**	cum	0.45	5734.36	2580.46	Additional Item	No	By over all savings in the work	PWD SR 2021-22 Volume - I	
E6	Providing **precast slab of 230mm thick** including cost of all materials, labour, curing, transportation, loading unloading, etc., complete as per the direction of engineer in charge - Data rate	Sqm	4.84	4584.17	22187.38	Additional Item	No	By over all savings in the work	Approved Data Rate	
	Total				**48632.92**					

Percentage Excess $\frac{\text{48632.92}}{\text{Approved Tender Amount } \text{2804266.75}} \times 100 =$ 1.73%

Assistant Engineer
New Ward No. 15

Assistant Executive Engineer
Vidyaranyapura Sub Division
BBMP

Assistant Executive Engineer
Vidyaranyapura Sub Division
B.B.M.P, Bangalore - 97

Executive Engineer
Byatarayanapura Division
BBMP

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ